Digitally signed by John F. Lewis-Smith, PE
Date: 2020.07.01 16:02:20-05'00'

SECTION 210500

COMMON WORK RESULTS FOR FIRE SUPPRESSION

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Pipe, fittings, valves, and connections for combination sprinkler and standpipe systems.

1.2 RELATED REQUIREMENTS

A. Section 078400 - Firestopping.

B. Section 211300 - Fire-Suppression Sprinkler Systems: Sprinkler systems design.

1.3 REFERENCE STANDARDS

A. ASME A112.18.1 - Plumbing Supply Fittings; 2012.

B. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Qualifications; 2015.

C. ASME B16.1 - Gray Iron Pipe Flanges and Flanged Fittings: Classes 25, 125, and 250; 2010.

D. ASME B16.3 - Malleable Iron Threaded Fittings: Classes 150 and 300; 2011.

E. ASME B16.4 - Gray Iron Threaded Fittings: Classes 125 and 250; 2011.

F. ASME B16.9 - Factory-Made Wrought Buttwelding Fittings; 2012.

G. ASTM A53/A53M - Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless; 2012.

H. ASTM A269/A269M - Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service; 2015.

I. ASTM A536 - Standard Specification for Ductile Iron Castings; 1984 (Reapproved 2014).

J. ASTM A795/A795M - Standard Specification for Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use; 2013.

K. ASTM C592 - Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type); 2013.

L. ASTM E814 - Standard Test Method for Fire Tests of Through-Penetration Fire Stops; 2013a.

M. ASTM F438 - Standard Specification for Socket-Type Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 40; 2015.

N. ASTM F439 - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80; 2013.

O. ASTM F442/F442M - Standard Specification for Chlorinated Poly(Vinyl Chloride) (CPVC) Plastic Pipe (SDR-PR); 2013.

P. ASTM F493 - Standard Specification for Solvent Cements for Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe and Fittings; 2014.

Q. AWS D1.1/D1.1M - Structural Welding Code - Steel; 2015.

R. AWWA C105/A21.5 - Polyethylene Encasement for Ductile-Iron Pipe Systems; 2010.

S. AWWA C110/A21.10 - Ductile-Iron and Gray-Iron Fittings; 2012.

T. AWWA C111/A21.11 - Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings; 2012.

U. AWWA C151/A21.51 - Ductile-Iron Pipe, Centrifugally Cast; 2009.

V. AWWA C606 - Grooved and Shouldered Joints; 2011.

W. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

X. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

Y. UL 262 - Gate Valves for Fire-Protection Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

Z. UL 312 - Check Valves for Fire-Protection Service; Underwriters Laboratories Inc.; Current Edition, Including All Revisions.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide manufacturers catalogue information. Indicate valve data and ratings.

C. Shop Drawings: Indicate pipe materials used, jointing methods, supports, floor and wall penetration seals. Indicate installation, layout, weights, mounting and support details, and piping connections.

D. Project Record Documents: Record actual locations of components and tag numbering.

E. Operation and Maintenance Data: Include installation instructions and spare parts lists.

1.5 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this section with minimum three years documented experience.

B. Valves: Bear UL label or marking. Provide manufacturer's name and pressure rating marked on valve body.

C. Products Requiring Electrical Connection: Listed and classified as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver and store valves in shipping containers, with labeling in place.

B. Provide temporary protective coating on cast iron and steel valves.

C. Provide temporary end caps and closures on piping and fittings. Maintain in place until installation.

PART 2 PRODUCTS

2.1 FIRE PROTECTION SYSTEMS

A. Sprinkler Systems: Conform work to NFPA 13.

B. Welding Materials and Procedures: Conform to ASME Code.

2.2 BURIED PIPING

A. Steel Pipe: ASTM A53/A53M Schedule 40 or ASTM A795 Standard Weight, black, with AWWA C105 polyethylene jacket, or double layer, half-lapped polyethylene tape.
   1. Steel Fittings: ASME B16.9, wrought steel, buttwelded; with double layer, half-lapped polyethylene tape.
   2. Cast Iron Fittings: ASME B16.1, flanges and flanged fittings.
   3. Joints: Welded in accordance with AWS D1.1.

B. Cast Iron Pipe: AWWA C151/A21.51.
   1. Fittings: AWWA C110, standard thickness.
   2. Joints: AWWA C111, rubber gasket.
   3. Mechanical Couplings: Shaped composition sealing gasket, steel bolts, nuts, and washers.

2.3 ABOVE GROUND PIPING

A. Steel Pipe: ASTM A795 Schedule 10 or ASTM A53 Schedule 40, black.
   1. Steel Fittings: ASME B16.9, wrought steel, buttwelded.
   2. Cast Iron Fittings: ASME B16.1, flanges and flanged fittings and ASME B16.4, threaded fittings.
   3. Malleable Iron Fittings: ASME B16.3, threaded fittings.
   4. Mechanical Grooved Couplings: Malleable iron housing clamps to engage and lock, "C" shaped elastomeric sealing gasket, steel bolts, nuts, and washers; galvanized for galvanized pipe.

5. Mechanical Formed Fittings: Carbon steel housing with integral pipe stop and O-ring pocked and O-ring, uniformly compressed into permanent mechanical engagement onto pipe.

B. CPVC Pipe: ASTM F442/F442M, SDR 13.5.
1. Fittings: ASTM F438 Schedule 40, or ASTM F439 schedule 80, CPVC.
2. Joints: Solvent welded, using ASTM F493 cement.

2.4 PIPE SLEEVES

A. Vertical Piping:
1. Sleeve Length: 1 inch above finished floor.
2. Provide sealant for watertight joint.

B. Pipe Passing Through Below Grade Exterior Walls:
1. Zinc coated or cast iron pipe.
2. Provide watertight space with link rubber or modular seal between sleeve and pipe on both pipe ends.

C. Not required for wall hydrants for fire department connections or in drywall construction.

D. Clearances:
1. Wall, Floor, Floor, Partitions, and Beam Flanges: 1 inch greater than external; pipe diameter.
2. All Rated Openings: Caulked tight with fire stopping material conforming to ASTM E814 in accordance with Firestopping section to prevent the spread of fire, smoke, and gases.

2.5 MANUFACTURED SLEEVE-SEAL SYSTEMS

A. Modular/Mechanical Seal:
1. Synthetic rubber interlocking links continuously fill annular space between pipe and wall/casing opening.
2. Provide watertight seal between pipe and wall/casing opening.
3. Elastomer element size and material in accordance with manufacturer's recommendations.
4. Glass reinforced plastic pressure end plates.

2.6 ESCUTCHEONS

A. Material:
1. Fabricate from nonferrous metal.
2. Chrome-plated except when 300 series, ASTM A269/A269M stainless steel is provided.
3. Metals and Finish: Comply with ASME A112.18.

B. Construction:
1. One-piece for mounting on chrome-plated tubing or pipe and one-piece or split-pattern type elsewhere.
2. Internal spring tension devices or setscrews to maintain a fixed position against a surface.

2.7 PIPE HANGERS AND SUPPORTS

A. Hangers for Pipe Sizes 1/2 to 1-1/2 inch: Malleable iron, adjustable swivel, split ring.

B. Hangers for Pipe Sizes 2 inches and Over: Carbon steel, adjustable, clevis.

C. Multiple or Trapeze Hangers: Steel channels with welded spacers and hanger rods.

D. Wall Support for Pipe Sizes to 3 inches: Cast iron hook.

E. Wall Support for Pipe Sizes 4 inches and Over: Welded steel bracket and wrought steel clamp.

F. Vertical Support: Steel riser clamp.

G. Floor Support: Cast iron adjustable pipe saddle, lock nut, nipple, floor flange, and concrete pier or steel support.

2.8 MECHANICAL COUPLINGS

A. Rigid Mechanical Couplings for Grooved Joints:
1. Dimensions and Testing: Comply with AWWA C606.

2. Minimum Working Pressure: 300 psig.
3. Housing Material: Fabricate of ductile iron conforming to ASTM A536.
4. Housing Coating: Factory applied orange enamel or _____.
5. Gasket Material: EPDM suitable for operating temperature range from minus 30 degrees F to 230 degrees F.
6. Bolts and Nuts: Hot dipped galvanized or zinc electroplated steel

2.9 GATE VALVES

A. Up to and including 2 inches:
1. Bronze body, bronze trim, rising stem, handwheel, solid wedge or disc, threaded ends.

B. Over 2 inches:
1. Iron body, bronze trim, rising stem pre-grooved for mounting tamper switch, handwheel, OS&Y, solid rubber covered bronze or cast iron wedge, flanged ends.

C. Over 4 inches:
1. Iron body, bronze trim, non-rising stem with bolted bonnet, solid bronze wedge, flanged ends, iron body indicator post assembly.

2.10 GLOBE OR ANGLE VALVES

A. Up to and including 2 inches:
1. Bronze body, bronze trim, rising stem and handwheel, inside screw, renewable rubber disc, threaded ends, with backseating capacity repackable under pressure.

B. Over 2 inches:
1. Iron body, bronze trim, rising stem, handwheel, OS&Y, plug-type disc, flanged ends, renewable seat and disc.

2.11 BUTTERFLY VALVES

A. Bronze Body:
1. Stainless steel disc, resilient replaceable seat, threaded or grooved ends, extended neck, handwheel and gear drive and integral indicating device, and built-in tamper proof switch rated 10 amp at 115 volt AC.

B. Cast or Ductile Iron Body
1. Cast or ductile iron, chrome or nickel plated ductile iron or aluminum bronze disc, resilient replaceable EPDM seat, wafer, lug, or grooved ends, extended neck, handwheel and gear drive and integral indicating device, and internal tamper switch rated 10 amp at 115 volt AC.

2.12 CHECK VALVES

A. Up to and including 2 inches:
1. Bronze body and swing disc, rubber seat, threaded ends.

B. Over 2 inches:
1. Iron body, bronze trim, swing check with rubber disc, renewable disc and seat, flanged ends with automatic ball check.

C. 4 inches and Over:
1. Iron body, bronze disc, stainless steel spring, resilient seal, threaded, wafer, or flanged ends.

2.13 DRAIN VALVES

A. Compression Stop:
1. Bronze with hose thread nipple and cap.

B. Ball Valve:
1. Brass with cap and chain, 3/4 inch hose thread.

PART 3 EXECUTION

3.1 PREPARATION

A. Ream pipe and tube ends. Remove burrs.

B. Remove scale and foreign material, from inside and outside, before assembly.

C. Prepare piping connections to equipment with flanges or unions.

3.2 INSTALLATION

A. Install sprinkler system and service main piping, hangers, and supports in accordance with NFPA 13.

B. The entire building shall be provided with a fire protection sprinkler system.

C. Prepare design documents including shop drawings and hydraulic calculations in accordance with NFPA 13 and submit to Authority Having Jurisdiction for approval prior to installation. Design shall be performed by a licensed Professional Engineer.

D. Route piping in orderly manner, plumb and parallel to building structure. Maintain gradient.

E. Install piping to conserve building space, to not interfere with use of space and other work.

F. Piping shall be concealed where routed in finished spaces.

G. Group piping whenever practical at common elevations.

H. Sleeve pipes passing through partitions, walls, and floors.

I. Install piping to allow for expansion and contraction without stressing pipe, joints, or connected equipment.

J. Inserts:
   1. Provide inserts for placement in concrete formwork.
   2. Provide inserts for suspending hangers from reinforced concrete slabs and sides of reinforced concrete beams.
   3. Provide hooked rod to concrete reinforcement section for inserts carrying pipe over 4 inches.
   4. Where concrete slabs form finished ceiling, locate inserts flush with slab surface.

K. Pipe Hangers and Supports:
   1. Install hangers to provide minimum 1/2 inch space between finished covering and adjacent work.
   2. Place hangers within 12 inches of each horizontal elbow.
   3. Use hangers with 1-1/2 inch minimum vertical adjustment. Design hangers for pipe movement without disengagement of supported pipe.
   4. Support vertical piping at every other floor. Support riser piping independently of connected horizontal piping.
   5. Where several pipes can be installed in parallel and at same elevation, provide multiple or trapeze hangers.
   6. Support piping from top chord of bar joists. Support from deck or bottom chord is not acceptable.

L. Slope piping and arrange systems to drain at low points. Use eccentric reducers to maintain top of pipe level.

M. Prepare pipe, fittings, supports, and accessories for finish painting. Where pipe support members are welded to structural building framing, scrape, brush clean, and apply one coat of zinc rich primer to welding.

N. Do not penetrate building structural members unless indicated.

O. Provide sleeves when penetrating footings, floors, and walls. Seal pipe and sleeve penetrations to achieve fire resistance equivalent to fire separation required.
   1. Underground Piping: Caulk pipe sleeve watertight with lead and oakum or mechanically expandable chloroprene inserts with bitumen sealed metal components.
   2. Aboveground Piping:
      a. Pack solid using mineral fiber conforming to ASTM C592.

b. Fill space with an elastomer caulk to a depth of 0.50 inch where penetrations occur between conditioned and unconditioned spaces.

3. All Rated Openings: Caulk tight with fire stopping material conforming to ASTM E814 in accordance with Firestopping section to prevent the spread of fire, smoke, and gases.
4. Caulk exterior wall sleeves watertight with lead and oakum or mechanically expandable chloroprene inserts with mastic-sealed components.

P. Manufactured Sleeve-Seal Systems:
1. Install manufactured sleeve-seal systems in sleeves located in grade slabs and exterior concrete walls at piping entrances into building.
2. Provide sealing elements of the size, quantity, and type required for the piping and sleeve inner diameter or penetration diameter.
3. Locate piping in center of sleeve or penetration.
4. Install field assembled sleeve-seal system components in annular space between sleeve and piping.
5. Tighten bolting for a water-tight seal.
6. Install in accordance with manufacturer's recommendations.

Q. Escutcheons:
1. Install and firmly attach escutcheons at piping penetrations into finished spaces.
2. Provide escutcheons on both sides of partitions separating finished areas through which piping passes.
3. Use chrome plated escutcheons in occupied spaces and to conceal openings in construction.

R. When installing more than one piping system material, ensure system components are compatible and joined to ensure the integrity of the system. Provide necessary joining fittings. Ensure flanges, union, and couplings for servicing are consistently provided.

S. Install valves with stems upright or horizontal, not inverted. Remove protective coatings prior to installation.

T. Provide gate valves for shut-off or isolating service.

U. Provide drain valves at main shut-off valves, low points of piping and apparatus.

END OF SECTION

SECTION 210523

GENERAL-DUTY VALVES FOR WATER-BASED FIRE-SUPPRESSION PIPING

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Two-piece ball valves with indicators.

B. Bronze butterfly valves with indicators.

C. Iron butterfly valves with indicators.

D. Check valves.

E. Bronze OS&Y gate valves.

F. Iron OS&Y gate valves.

G. NRS gate valves.

H. Indicator posts.

I. Trim and drain valves.

1.2 RELATED REQUIREMENTS

A. Section 210500 - Common Work Results for Fire Suppression: Pipe and fittings.

B. Section 210553 - Identification for Fire Suppression Piping and Equipment.

C. Section 211300 - Fire Suppression Sprinklers.

D. Section 283100 - Fire Detection and Alarm.

1.3 ABBREVIATIONS AND ACRONYMS

A. EPDM: Ethylene-propylene diene monomer.

B. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.

C. NRS: Non-rising stem.

D. OS&Y: Outside screw and yoke.

E. PTFE: Polytetrafluoroethylene.

F. SBR: Styrene-butadiene rubber.

1.4 REFERENCE STANDARDS

A. ASME BPVC-IX - Boiler and Pressure Vessel Code, Section IX - Welding, Brazing, and Fusing Qualifications; 2015.

B. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

1.5 SUBMITTALS

A. Product Data: Provide data on valves including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.

B. Warranty: Submit manufacturer warranty and ensure that forms have been completed in Owner's name and registered with manufacturer.

C. Operation and Maintenance Data: Include manufacturer's descriptive literature, operating instructions, maintenance and repair data, and parts listings.

1.6 QUALITY ASSURANCE

A. Manufacturer:

1. Obtain valves for each valve type from single manufacturer.
2. Company must specialize in manufacturing products specified in this section, with not less than three years of documented experience.

B. Where listed products are specified, provide products listed, classified, and labeled by Underwriters Laboratories Inc. (UL), FM Global, or testing firm acceptable to authorities having jurisdiction as suitable for the purpose indicated.

C. Welding Materials and Procedures: Conform to ASME BPVC-IX.

D. Installer and Maintenance Contractor Qualifications:
   1. Company specializing in performing the work of this section with minimum five years documented experience.
   2. Trained and approved by manufacturer to design, install, test and maintain the equipment specified herein.
   3. Complies with manufacturer's certification requirements.
   4. Complies with manufacturer's insurance requirements.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:
   1. Protect internal parts against rust and corrosion.
   2. Set valves open to minimize exposure of functional surfaces.

B. Use the following precautions during storage:
   1. Maintain valve end protection and protect flanges and specialties from dirt.
      a. Provide temporary inlet and outlet caps.
      b. Maintain caps in place until installation.
   2. Store valves in shipping containers and maintain in place until installation.
      a. Store valves indoors and maintain at higher than ambient dew point temperature.
      b. If outdoor storage is unavoidable, store valves off the ground in watertight enclosures.

C. Use the following precautions for handling:
   1. Do not use operating handles or stems as lifting or rigging points.

PART 2 PRODUCTS

2.1 GENERAL REQUIREMENTS

A. Comply with NFPA 13 and NFPA 13R for valves.

B. Valve Pressure Ratings: Not less than minimum pressure rating indicated or higher as required.

C. Valve Sizes: Same as upstream piping unless otherwise indicated.

D. Valve Actuator Types:
   1. Worm-gear actuator with handwheel for quarter-turn valves, except trim and drain valves.
   2. Handwheel: For other than quarter-turn trim and drain valves.
   3. Hand-lever: For quarter-turn trim and drain valves 2 NPS and smaller.

2.2 TWO-PIECE BALL VALVES WITH INDICATORS

A. Description:
   1. Minimum Pressure Rating: 175 psig.
   2. Body Design: Two piece.
   3. Body Material: Forged brass or bronze.
   4. Port Size: Full or standard.
   5. Seat: PTFE.
   6. Stem: Bronze or stainless steel.
   7. Ball: Chrome-plated brass.
   8. Actuator: Worm gear or traveling nut.
   9. Supervisory Switch: Internal or external.

2.3 BRONZE BUTTERFLY VALVES WITH INDICATORS

A. Minimum Pressure Rating: 175 psig.

B. Body Material: Bronze.

C. Seat: EPDM.

D. Stem: Bronze or stainless steel.

E. Disc: Bronze with EPDM coating.

F. Actuator: Worm gear or traveling nut.

G. Supervisory Switch: Internal or external.

2.4 IRON BUTTERFLY VALVES WITH INDICATORS

A. Minimum Pressure Rating: 175 psig.

B. Body Material: Cast or ductile iron with nylon, EPDM, epoxy, or polyamide coating.

C. Seat: EPDM.

D. Stem: Stainless steel.

E. Disc: Ductile iron, nickel plated.

F. Actuator: Worm gear or traveling nut.

G. Supervisory Switch: Internal or external.

H. Body Design: Grooved-end connections.

2.5 CHECK VALVES

A. Minimum Pressure Rating: 175 psig.

B. Type: Center guided check valve.

C. Body Material: Cast iron, ductile iron.

D. Center guided check with elastomeric seal.

E. Hinge Spring: Stainless steel.

F. End Connections: Flanged, grooved, or threaded.

2.6 BRONZE OS&Y GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Bronze or brass.

C. Wedge: One-piece bronze or brass.

D. Wedge Seat: Bronze.

E. Stem: Bronze or brass.

F. Packing: Non-asbestos PTFE.

G. Supervisory Switch: External.

H. End Connections: Threaded.

2.7 IRON OS&Y GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Cast or ductile iron.

C. Wedge: Cast or ductile iron, or bronze with elastomeric coating.

D. Wedge Seat: Cast or ductile iron, or bronze with elastomeric coating.

E. Stem: Brass or bronze.

F. Packing: Non-asbestos PTFE.

G. Supervisory Switch: External.

H. End Connections: Flanged.

2.8 NRS GATE VALVES

A. Minimum Pressure Rating: 175 psig.

B. Body and Bonnet Material: Cast or ductile iron.

C. Wedge: Cast or ductile iron with elastomeric coating.

D. Stem: Brass or bronze.

E. Packing: Non-asbestos PTFE.

F. Supervisory Switch: External.

G. End Connections: Flanged.

2.9 INDICATOR POSTS

A. Type: Underground.

B. Base Barrel Material: Cast or ductile iron.

C. Cap: Cast or ductile iron.

D. Operation: Wrench.

2.10 TRIM AND DRAIN VALVES

A. Ball Valves:

1. Description:

a. Pressure Rating: 175 psig.

b. Body Design: Two piece.

c. Body Material: Forged brass or bronze.

d. Port Size: Full or standard.

e. Seat: PTFE.

f. Stem: Bronze or stainless steel.

g. Ball: Chrome-plated brass.

h. Actuator: Hand-lever.

B. Angle Valves:

1. Description:

a. Pressure Rating: 175 psig.

b. Body Material: Brass or bronze.

c. Ends: Threaded.

d. Stem: Bronze.

e. Disc: Bronze.

f. Packing: Asbestos free.

g. Handwheel: Malleable iron, bronze, or aluminum.

C. Globe Valves:

1. Description:

a. Pressure Rating: 175 psig.

b. Body Material: Bronze with integral seat and screw-in bonnet.

c. Ends: Threaded.

d. Stem: Bronze.

e. Disc Holder and Nut: Bronze.

f. Disc Seat: Nitrile.

g. Packing: Asbestos free.

h. Handwheel: Malleable iron, bronze, or aluminum.

PART 3 EXECUTION

3.1 EXAMINATION

A. Confirm valve interior to be free of foreign matter and corrosion.

B. Remove packing materials.

C. Examine guides and seats by operating valves from the fully open position to the fully closed position.

D. Examine valve threads and mating pipe for form and cleanliness.

3.2 INSTALLATION

A. Comply with specific valve installation requirements and application in the following Sections:

B. Install listed fire protection shutoff valves supervised-open, located to control sources of water supply except from fire department connections.

1. Install permanent identification signs indicating portion of system controlled by each valve.

C. Install check valve in water supply connections and backflow preventer at potable water supply connections.

D. Valves in horizontal piping installed with stem at or above the pipe center.

E. Position valves to allow full stem movement.

F. Install valve tags. Comply with Section 210553 requirements for valve tags, schedules, and signs on surfaces concealing valves; and the appropriate NFPA standard applying to the piping system in which valves are installed.

END OF SECTION

SECTION 210553

IDENTIFICATION FOR FIRE SUPPRESSION PIPING AND EQUIPMENT

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Nameplates.

B. Tags.

C. Stencils.

D. Pipe Markers.

1.2 REFERENCE STANDARDS

1.3 SUBMITTALS

A. List: Submit list of wording, symbols, letter size, and color coding for mechanical identification.

B. Chart and Schedule: Submit valve chart and schedule, including valve tag number, location, function, and valve manufacturer's name and model number.

C. Product Data: Provide manufacturers catalog literature for each product required.

PART 2 PRODUCTS

2.1 NAMEPLATES

A. Description: Laminated three-layer plastic with engraved letters.

2.2 TAGS

A. Plastic Tags: Laminated three-layer plastic with engraved black letters on light contrasting background color. Tag size minimum 1-1/2 inch diameter.

B. Metal Tags: Brass with stamped letters; tag size minimum 1-1/2 inch diameter with smooth edges.

C. Valve Tag Chart: Typewritten letter size list in anodized aluminum frame.

2.3 STENCILS

A. Stencils: With clean cut symbols and letters of following size:

1. 3/4 to 1-1/4 inch Outside Diameter of Insulation or Pipe: 8 inch long color field, 1/2 inch high letters.
2. 1-1/2 to 2 inch Outside Diameter of Insulation or Pipe: 8 inch long color field, 3/4 inch high letters.
3. 2-1/2 to 6 inch Outside Diameter of Insulation or Pipe: 12 inch long color field, 1-1/4 inch high letters.
4. Equipment: 2-1/2 inch high letters.

2.4 PIPE MARKERS

A. Plastic Pipe Markers: Factory fabricated, flexible, semi- rigid plastic, preformed to fit around pipe or pipe covering; minimum information indicating flow direction arrow and identification of fluid being conveyed.

B. Plastic Tape Pipe Markers: Flexible, vinyl film tape with pressure sensitive adhesive backing and printed markings.

C. Underground Plastic Pipe Markers: Bright colored continuously printed plastic ribbon tape, minimum 6 inches wide by 4 mil thick, manufactured for direct burial service.

PART 3 EXECUTION

3.1 PREPARATION

A. Degrease and clean surfaces to receive adhesive for identification materials.

3.2 INSTALLATION

A. Install nameplates with corrosive-resistant mechanical fasteners, or adhesive. Apply with sufficient adhesive to ensure permanent adhesion and seal with clear lacquer.

B. Install tags with corrosion resistant chain.

C. Install plastic pipe markers in accordance with manufacturer's instructions.

D. Install plastic tape pipe markers complete around pipe in accordance with manufacturer's instructions.

E. Install underground plastic pipe markers 6 to 8 inches below finished grade, directly above buried pipe.

F. Use tags on piping 3/4 inch diameter and smaller.

END OF SECTION

SECTION 211300

FIRE SUPPRESSION SPRINKLERS

PART 1 GENERAL

1.1 SECTION INCLUDES

A. Wet-pipe sprinkler system.

B. Dry-pipe sprinkler system.

C. System design, installation, and certification.

D. Fire department connections.

1.2 RELATED REQUIREMENTS

A. Section 210500 - Common Work Results for Fire Suppression: Pipe, fittings, and valves.

B. Section 220553 - Identification for Plumbing Piping and Equipment.

1.3 REFERENCE STANDARDS

A. FM P7825 - Approval Guide; Factory Mutual Research Corporation; current edition.

B. ICC-ES AC01 - Acceptance Criteria for Expansion Anchors in Masonry Elements; 2012.

C. ICC-ES AC106 - Acceptance Criteria for Predrilled Fasteners (Screw Anchors) in Masonry Elements; 2012.

D. ICC-ES AC193 - Acceptance Criteria for Mechanical Anchors in Concrete Elements; 2013.

E. ICC-ES AC308 - Acceptance Criteria for Post-Installed Adhesive Anchors in Concrete Elements; 2013.

F. NFPA 13 - Standard for the Installation of Sprinkler Systems; 2016.

G. UL (DIR) - Online Certifications Directory; current listings at database.ul.com.

1.4 SUBMITTALS

A. See Division 1 Section - Administrative Requirements, for submittal procedures.

B. Product Data: Provide data on sprinklers, valves, and specialties, including manufacturers catalog information. Submit performance ratings, rough-in details, weights, support requirements, and piping connections.

C. Shop Drawings:

1. Submit preliminary layout of finished ceiling areas indicating only sprinkler locations coordinated with ceiling installation. Additionally, indicate general routing of piping for review by Architect.
2. Indicate hydraulic calculations, detailed pipe layout, hangers and supports, sprinklers, components and accessories. Indicate system controls.
3. Submit shop drawings, product data, and hydraulic calculations to authority having jurisdiction for approval. Drawings and calculations shall be stamped by a licenced professional engineer.
4. Installation shall be fully coordinated with structure and all other trades. Coordination shall be performed with installed conditions, not just the construction drawings. Rework of sprinkler piping due to conflicts with field conditions shall be performed without cost to the Owner or Engineer.

D. Project Record Documents: Record actual locations of sprinklers and deviations of piping from drawings. Indicate drain and test locations.

E. Operation and Maintenance Data: Include components of system, servicing requirements, record drawings, inspection data, replacement part numbers and availability, and location and numbers of service depot.

F. Maintenance Materials: Furnish the following for Owner's use in maintenance of project.

1. See Section 016000 - Product Requirements, for additional provisions.
2. Extra Sprinklers: Type and size matching those installed, in quantity required by referenced NFPA design and installation standard.

3. Sprinkler Wrenches: For each sprinkler type.

1.5 QUALITY ASSURANCE

A. Maintain one copy of referenced design and installation standard on site.

B. Conform to UL requirements.

C. Designer Qualifications: Design system under direct supervision of a Professional Engineer experienced in design of this type of work and licensed in Kansas.

D. Equipment and Components: Provide products that bear UL label or marking.

E. Products Requiring Electrical Connection: Listed and classified by Underwriters Laboratories Inc., as suitable for the purpose specified and indicated.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Store products in shipping containers and maintain in place until installation. Provide temporary inlet and outlet caps. Maintain caps in place until installation.

1.7 EXTRA MATERIALS

A. Provide extra sprinklers of type and size matching those installed, in quantity required by referenced NFPA design and installation standard.

B. Provide suitable wrenches for each sprinkler type.

C. Provide metal storage cabinet located adjacent to alarm valve.

PART 2 PRODUCTS

2.1 SPRINKLER SYSTEM

A. Sprinkler System: Provide coverage for entire building.

B. Occupancy: Comply with NFPA 13.

C. Water Supply: Determine volume and pressure from water flow test data.

D. Interface system with building fire and smoke alarm system.

E. Provide fire department connections at locations coordinated with Fire Department.

F. Storage Cabinet for Spare Sprinklers and Tools: Steel, located adjacent to alarm valve.

G. Pipe Hanger Fasteners: Attach hangers to structure using appropriate fasteners, as follows:
1. Concrete Wedge Expansion Anchors: Complying with ICC-ES AC193.
2. Masonry Wedge Expansion Anchors: Complying with ICC-ES AC01.
3. Concrete Screw Type Anchors: Complying with ICC-ES AC193.
4. Masonry Screw Type Anchors: Complying with ICC-ES AC106.
5. Concrete Adhesive Type Anchors: Complying with ICC-ES AC308.
6. Other Types: As required.

2.2 SPRINKLERS

A. Suspended Ceiling Type: Recessed or concealed pendant type with matching push on escutcheon or cover plate.
1. Finish: Enamel, color white.
2. Escutcheon Plate Finish: Enamel, color white.
3. Cover Plate Finish: White enamel.
4. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

B. Exposed Area Type: Standard upright type with guard.
1. Finish: Brass.
2. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

C. Sidewall Type: Recessed horizontal sidewall type with matching push on escutcheon plate .
1. Finish: Enamel, color white.
2. Escutcheon Plate Finish: Enamel, color white.

3. Fusible Link: Fusible solder link type temperature rated for specific area hazard.

D. Guards: Finish to match sprinkler finish.
1. Provide guards at all heads in back of house areas including linen and storage rooms.
2. Provide guards at all heads installed below 8' AFF.

2.3 PIPING SPECIALTIES

A. Dry Pipe Sprinkler Alarm Valve: Check type valve with divided seat ring, rubber faced clapper to automatically actuate water motor alarm, accelerator, and with the following additional capabilities and features:
1. Activate electric alarm.
2. Test and drain valve.
3. Externally resettable.
4. Replaceable internal components without removing valve from installed position.

B. Wet Pipe Sprinkler Alarm Valve: Check type valve with divided seat ring, rubber faced clapper to automatically actuate water motor alarm and electric alarm, with pressure retard chamber and variable pressure trim; with test and drain valve.

C. Backflow Preventer: Double check valve assembly backflow preventer with drain and OS & Y gate valve on each end. Coordinate requirements with Authority Having Jurisdiction.

D. Test Connections:
1. Backflow Preventer Test Connection:
a. Provide downstream of the backflow prevention assembly, listed hose valves with 2.5 inch National Standard male hose threads with cap and chain.

E. Electric Alarm: Electrically operated chrome plated gong with pressure alarm switch.

F. Water Flow Switch: Vane type switch for mounting horizontal or vertical, with two contacts; rated 10 amp at 125 volt AC and 2.5 amp at 24 volt DC.

G. Fire Department Connections:
1. Type: Flush mounted wall type with chrome plated finish.
2. Outlets: Two way with thread size to suit fire department hardware; threaded dust cap and chain of matching material and finish.
3. Drain: 3/4 inch automatic drip, outside.
4. Label: "Auto. Sprinkler".

2.4 AIR COMPRESSOR

A. Compressor: Single unit, electric motor driven, motor, motor starter, safety valves, check valves, air maintenance device incorporating electric pressure switch and unloader valve.

B. Electrical Characteristics:
1. 1/3 hp.
2. 125 volts, single phase, 60 Hz.

PART 3 EXECUTION

3.1 INSTALLATION

A. Install in accordance with referenced NFPA design and installation standard.

B. Install equipment in accordance with manufacturer's instructions.

C. Install buried shut-off valves in valve box. Provide post indicator.

D. Provide approved backflow preventer assembly at sprinkler system water source connection.

E. Locate fire department connection with sufficient clearance from walls, obstructions, or adjacent siamese connectors to allow full swing of fire department wrench handle. Coordinate with Authority Having Jurisdiction.

F. Place pipe runs to minimize obstruction to other work.

G. Place piping in concealed spaces above finished ceilings.

H. Center sprinklers in two directions in ceiling tile and provide piping offsets as required.

I. Apply masking tape or paper cover to ensure concealed sprinklers, cover plates, and sprinkler escutcheons do not receive field paint finish. Remove after painting. Replace painted sprinklers.

J. Flush entire piping system of foreign matter.

K. Hydrostatically test entire system.

L. Required tests must be witnessed by authority having jurisdiction.

M. Public areas must have concealed or recessed heads. Concealed or recessed ceiling or sidewall heads may be used in apartments.

N. Areas subject to freezing shall be provided with dry type heads.

3.2 INTERFACE WITH OTHER PRODUCTS

A. Ensure required devices are installed and connected as required to fire alarm system.

END OF SECTION