

Architecture  
Interior Design  
Graphic Design  
Facility Planning

**NOTICE TO ALL CONTRACTORS & BIDDERS**  
January 6, 2021

**Stonepost Lofts**  
**At Washington; Hays, KS**  
Project No. 19-3009

**ADDENDUM NO. 5**

YOU ARE INSTRUCTED TO READ AND TO NOTE THE FOLLOWING DESCRIBED CHANGES, CORRECTIONS, CLARIFICATIONS, OMISSIONS, DELETIONS, ADDITIONS, APPROVALS AND STATEMENTS PERTINENT TO THE CONTRACT BID AND CONSTRUCTION DOCUMENTS.

THIS ADDENDUM IS A PART OF THE CONTRACT BID AND CONSTRUCTION DOCUMENTS AND SHALL GOVERN IN THE PERFORMANCE OF THE WORK.

**Architectural**

1. Sheet A3.1, A3.2, Windows & Glass Block; attached contractor to remove and replace all caulking at window and door frames, to be water and weather tight. In addition at glass block openings, and during tuckpointing contractor shall remove all loose grout, and proper tuckpoint all joints to ensure proper water and weather tightness.
2. Sheet A5.1, Roof Ladders; During Tuckpointing, ensure ladder supports and anchors are properly grouted and secure. Replace anchors and supports if required to ensure they are secure and safe for use.
3. Sheet A5.1, Roof Drains 1926 addition; Remove and replace two existing roof drain strainers with dual overflow type with High & Low.

Jeff Gillam  
Charles Renz  
Mark Regier  
Maggie Gillam  
Chris Gillam

END OF ADDENDUM NO. 5

Attachments:

The following sheets have been changed per Addendum 5:  
A3.1, A3.2, A5.1 (24x36 electronic copy)



730 N. Ninth (67401)  
P.O. Box 2928  
Salina, KS 67402-2928  
(785) 827-0386  
Fax (785) 827-0392